
Switchgear busbar modification qualification



Overview

The first series of standards for switchgear and controlgear assembly IEC 60439 was published in 1973.

Key Takeaways

Busbar modifications in switchgear require strict adherence to design standards, type testing, and verification of thermal, mechanical, and electrical performance to ensure safety and reliability.

Key Qualification Requirements

Standards Compliance: Any busbar modification must comply with international and national standards such as IEC 60439-1, IEC 61439, and ANSI/IEEE for medium- and low-voltage switchgear. These standards define requirements for electrical performance, mechanical strength, insulation, and thermal limits, ensuring that modified busbars operate safely under rated and fault conditions. Type Testing and Certification: Modified busbars often require type test certificates issued by recognized authorities like ASTA (UK) or equivalent.

Tests include short-circuit withstand, temperature-rise, internal arcing fault, and conditional short-circuit current tests. These tests verify that the busbar can handle rated currents and fault conditions without deformation, overheating, or insulation failure. Thermal and Mechanical Verification: Busbars must maintain thermal stability under rated load and short-circuit conditions.

IE

© 2026 CJC FIBRE CONSULTANTS - All rights reserved

C 61439 specifies maximum temperature limits (e.g., 140°C for low-voltage busbars) and requires verification of mechanical integrity to withstand electromagnetic forces during faults. Proper spacing, support, and material selection (copper or aluminum) are critical for safe operation. Modification Practices: Modifications may include busbar extensions, replacement of damaged busbars, or integration with new protection devices.

All modifications should preserve the original switchgear's form, fit, and function, ensuring compatibility with existing panels and enclosures. Preventive maintenance and inspection are recommended to identify wear or contamination before and after modification. Documentation: Complete documentation is essential, including arrangement drawings, test procedures, oscillograms, photographs, and conclusive statements.

This ensures traceability and regulatory compliance, particularly when integrating modified busbars into operational systems.

Practical Considerations

Ensure site measurements match existing switchgear for extensions or retrofits. Use rigid, flat, or laminated busbars depending on current rating, space, and mechanical requirements. Verify coordination with protection devices to maintain system safety.

Conduct scheduled preventive maintenance post-modification to maintain reliability. Conclusion: Busbar modifications in switchgear are qualified through a combination of standards compliance, type testing, thermal and mechanical verification, proper modification practices, and thorough documentation. Adhering to these requirements ensures safe, reliable, and long-lasting operation of the modified switchgear system.

Article Content

Switchgear Modification / Retrofitting

Dismantle Flashover-damaged Busbar and Current Transformer and reinstall New Busbar and CT. Scheduled preventive maintenance to ensure switchgear

Busbar Design in Switchgear: Key Principles & Best

Looking for a safe, efficient, and standards-compliant busbar solution for your switchgear project? Our engineering team can help you choose the right

Guide_Normes_IEC 61439_GB

The first series of standards for switchgear and controlgear assembly IEC 60439 was published in 1973. Consequently, this series of standards has often been criticized and considered as difficult to

IEC 61439 Low Voltage Switchgear Design: Complete 2026 Guide

© 2026 CJC FIBRE CONSULTANTS - All rights reserved

IEC 61439 permits design rule verification of busbar short-circuit withstand strength through calculation or comparison with tested reference designs, provided all criteria including conductor dimensions,

IEC 61439 Standards-R1

EMC for the LVB product installed in the ArTu K is verified – Pass. All ABB SACE LVB products specially with Electronic releases are tested and comply to EMC requirements.

Switchboard Busbar Guide (2025): Design & Standards

Learn how switchboard busbars are designed, sized, and verified to IEC/UL. Compare Cu vs Al, spacing, and testing. Download the RFQ checklist.

IEC 61439 Design Verification & CE Guide

IEC 61439 design verification is the cornerstone process ensuring every low-voltage switchgear and controlgear assembly meets safety and performance requirements before

GAMBICA guide to BS EN 61439 Edition 2

In the UK, the new standard is described and embodied within the BS EN 61439 series, replacing the BS EN 60439 series. Either series can be used until 1 November 2014. From that date BS EN 60439-1 is

Switchgear Assembly Testing & Certification

Across Europe and Asia, high-voltage and low-voltage switchgear assemblies must be tested and certified for compliance with IEC standards, including IEC 62271. To demonstrate your product''s

Application Guide MNS-SG Low Voltage, Metal-Enclosed, Drawout Switchgear

General For over 30 years, ABB has been the global leader for low voltage switchgear and motor control centers (MNS). Drawing on a heritage of technology excellence and innovation, the MNS product

Switchgear Modification / Retrofitting

Switchgear Modification / Retrofitting Rejuvenate Your Switchgear Modernize Your Infrastructure. Maximize Your Investment Enhance the performance and lifespan

Testing and commissioning of MV/HV switchgear

Testing and commissioning precautions This article continues the series of articles dedicated to the erection, testing and commissioning of MV/HV

Layout 1

© 2026 CJC FIBRE CONSULTANTS - All rights reserved

Busbar Trunking Phase Transposition Unit [phase transposition BTU]: A busbar trunking unit which changes the relative positions of the phase conductors within the enclosure to balance inductive

UL Question Corner: Field modifications of UL Certified (Listed ...

That marking indicates the holes can be used in conjunction with specific wire connectors identified on the switchboard as a field installed accessory. Any other field modifications to the

Technical Application Papers No.11 Guidelines to the construction

In each test, the incoming circuit and the busbars are lo-aded to their rated current and as many outgoing circuits in a group are loaded to their rated current as necessary to distribute the incoming

New Zealand Certificate in Electrical Engineering (Switchgear Fitting ...

Where can I go? Graduates of this qualification will be qualified to work as a switchgear fitter or electrical installer in areas such as design, construction, installation, maintenance, and repair of switch and

Switchgear Compliance – Taps, Modifications, Interconnections – Part

Tapping into existing switchgear is considered a modification of the original UL listed product. Because such a modification could invalidate the original UL listing, city inspection agencies

Bespoke Switchgear Modifications and Upgrades

Bespoke Switchgear Modifications and Upgrades Switchgear Support Ltd are essentially a solution provider – clients often table a problem and we will advise the most technically capable, but

© 2026 CJC FIBRE CONSULTANTS - All rights reserved

Contact Us

Continue your research online:

Website: https://cjcconsultants.co.za
Technical inquiry: https://cjcconsultants.co.za/contact.html

This document is for preliminary research. Verify specifications against current standards, product documentation and project requirements.

© 2026 CJC FIBRE CONSULTANTS - All rights reserved